

- B2.3 Supply and installation of final circuit power installation, including:-
- MCB boards and accessories
 - Trunking and accessories
 - Cable, conduit and accessories
 - Socket outlets
 - Connection units
 - Floor Boxes
 - Power point as specified on the drawings
- B2.4 Supply and installation of final circuit lighting installation, including:-
- Switches
 - Motion sensors and by-pass switches if need
 - Lighting points for all lighting fittings as shown on the drawing
 - Timer and contactors
 - Trunking, cable, conduit and accessories
- B2.5 Alteration and addition of all existing Office light fittings (ceiling, trough, furniture etc.) including lamps transformer, ballast, wiring, conduit/ trunking, switch points as specified by the Lighting Designer.
- B2.6 Supply and installation of all new Office light fittings (ceiling, trough, furniture etc.) including lamps, transformer, ballast, wiring, conduit / trunking, switch points as indicated on the drawings & specified by the Lighting Designer.
- B2.7 Supply and installation of all emergency lighting (i.e. Exit Sign and battery pack for Office Lightings) as shown on drawings, including wiring, conduit/ trunking, switch points.
- B2.8 Supply and installation of trunking and conduit installation for AV system and intercom system.
- B2.9 Supply and installation of trunking and conduit installation for IT system, computer system and telephone system.
- B2.10 Supply and installation of trunking and conduit installation for Security system, i.e. CCTV system and door access system.
- B2.11 Supply and installation of the earthing protection including protective conductor for the low voltage distribution system and equipotential bonding to all extraneous conductive parts in the site area.
- B2.12 Not Applicable
- B2.13 Not Applicable
- B2.14 Not Applicable
- B2.15 Not Applicable
- B2.16 Not Applicable

